

# FLUKE TRMS Clamp-on meter

## Model 902 HVAC, CAT III 600V

- Tension 600.0Vdc and 600.0Vac (TRMS)
- Current 600.0A ac (TRMS) and 200 $\mu$ A dc
- Resistance 9999 ohms
- Continuity test
- Capacitance 1000 $\mu$ F
- Temperature T/C type K, -40/400°C (-14/752°F)
- 3 years warranty

Code	Description
902	Digital clamp-on meter with soft pouch, TL75 test leads, 80BK temperature probe

